REVISIONS			
REV	DESCRIPTION	DATE	APPROVED
А	REVISED TO ADD 3/4 LITE PANEL	02/11/2021	R.L.
В	REVISED TO ADD INSTALLATION DETAILS	03/15/2022	R.L.

#### NOTES:

- 1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH REQUIREMENTS OF THE 2018 IBC AND 2018 IRC.
- 2. WOOD FRAMING AND MASONRY OPENING TO BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO STRUCTURE. FRAMING AND MASONRY OPENING IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
- 3. WHERE SHIM OR BUCK THICKNESS IS LESS THAN 1-1/2" WINDOW UNITS MUST BE ANCHORED THROUGH THE FRAME IN ACCORDANCE WITH MANUFACTURER'S PUBLISHED INSTALLATION INSTRUCTIONS. ANCHORS SHALL BE SECURELY FASTENED DIRECTLY INTO MASONRY, CONCRETE OR OTHER STRUCTURAL SUBSTRATE MATERIAL.
- 4. WHERE WOOD BUCK THICKNESS IS 1-1/2" OR GREATER, BUCK SHALL BE SECURELY FASTENED TO MASONRY, CONCRETE OR OTHER STRUCTURAL SUBSTRATE. WINDOW UNITS MAY BE ANCHORED THROUGH FRAME TO SECURED WOOD BUCK IN ACCORDANCE WITH MANUFACTURER'S PUBLISHED INSTALLATION INSTRUCTIONS.
- 5. WHERE 1X BUCK IS NOT USED DISSIMILAR MATERIALS MUST BE SEPARATED WITH APPROVED COATING OR MEMBRANE. SELECTION OF COATING OR MEMBRANE IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
- 6. BUCKS SHALL EXTEND BEYOND WINDOW INTERIOR FACE SO THAT FULL FRAME SUPPORT IS PROVIDED.
- 7. SHIM AS REQUIRED AT EACH ANCHOR LOCATION WITH LOAD BEARING SHIM. SHIM WHERE SPACE OF 1/16" OR GREATER OCCURS. MAXIMUM ALLOWABLE SHIM STACK TO BE 1/4".
- 8. SHIMS SHALL BE LOCATED, APPLIED AND MADE FROM MATERIALS AND THICKNESS CAPABLE OF SUSTAINING APPLICABLE LOADS.
- 9. WIND LOAD DURATION FACTOR Cd=1.6 WAS USED FOR WOOD ANCHOR CALCULATIONS.
- 10. FRAME MATERIAL: CO-EXTRUDED PVC FOAM.
- 11. UNITS MUST BE GLAZED PER ASTM E1300, WITH SAFETY GLAZING.
- 12. APPROVED IMPACT PROTECTIVE SYSTEM <u>IS REQUIRED</u> FOR THIS PRODUCT IN WIND BORNE DEBRIS REGIONS.
- 13. FOR ANCHORING INTO WOOD FRAMING OR 2X BUCK USE #10 WOOD SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/4" MINIMUM EMBEDMENT INTO SUBSTRATE. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.

SHEET NO.

2

3 - 4

5 - 6

7 - 15

NOTES

16 - 17 | COMPONENTS

- 14. FOR ANCHORING INTO MASONRY/CONCRETE USE 3/16" TAPCONS WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/4" MINIMUM EMBEDMENT INTO SUBSTRATE WITH 2" MINIMUM EDGE DISTANCE. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
- 15. FOR ANCHORING INTO METAL STRUCTURE USE #10 SMS OR SELF DRILLING SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE 3 THREADS MINIMUM BEYOND STRUCTURE INTERIOR WALL. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
- 16. ALL FASTENERS TO BE CORROSION RESISTANT.
- 17. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BELOW:
  - A. WOOD MINIMUM SPECIFIC GRAVITY OF G=0.42
  - B. CONCRETE MINIMUM COMPRESSIVE STRENGTH OF 3,192 PSI.
  - C. MASONRY STRENGTH CONFORMANCE TO ASTM C-90, GRADE N, TYPE 1 (OR GREATER).
  - D. METAL STRUCTURE: STEEL 18GA, 33KSI OR ALUMINUM 6063-T5 .125" THICK MINIMUM
- 18. APPROVED CONFIGURATIONS: X, X/O, O/X, OX, XO, OX/O, XO/O, XX, XX/O, O/XX, OXX, XXO, OXX/O AND O/XXO, SEE SHEET 3.
- 19. SIDELITES ARE ASSEMBLED TO FRAME WITH #10 X 3" WOOD SCREWS LOCATED 4" FROM EACH END AND 19 1/8" MAX O.C. THEREAFTER AT JAMBS AND 4" FROM EACH END AND ONE AT MIDSPAN AT HEAD AND SILL.

SIGNED: 03/25/2022

NAN YA PLASTICS CORPORATION U.S.A.

8989 NORTH LOOP EAST
HOUSTON, TX 77029

SERIES "SLPS" GLAZED FIBERGLASS INSWING SIDE-HINGED DOOR W/SIDELITES, NON-IMPACT NOTES

DRAWN: DWG NO. REV A.R. 08-03315 B

SCALE NTS DATE 09/27/18 SHEET 1 OF 17

L. ROBERTO LOMAS P.E. 400 S. PALM AVE, INDIALANTIC, FL 32903 434-688-0609 rllomas@irlomaspe.com



Luis R. Lomas P.E. TX No.: 101889 Firm No: F-23130



TABLE OF CONTENTS


ELEVATION AND GLAZING DETAIL


APPROVED CONFIGURATIONS


ANCHORING LAYOUTS


INSTALLATION DETAILS

DESCRIPTION











EXTERIOR VIEW




\_\_\_\_\_ 73 5/16" ——



EXTERIOR VIEW

	REVISIONS		
REV	DESCRIPTION	DATE	APPROVED
А	REVISED TO ADD 3/4 LITE PANEL	02/11/2021	R.L.
В	REVISED TO ADD INSTALLATION DETAILS	03/15/2022	R.L.



SIGNED: 03/25/2022

82 7/16"

///

**FIXED** 

ALL APPROVED CONFIGURATIONS ARE SHOWN AS LEFT HAND ACTIVE, RIGHT HAND ACTIVE IS ALSO APPROVED.

**ACTIVE** 

SINGLE W/SIDELITE (MULL)

EXTERIOR VIEW

**FIXED** 


NAN YA PLASTICS CORPORATION U.S.A.
8989 NORTH LOOP EAST
HOUSTON, TX 77029


SERIES "SLPS" GLAZED FIBERGLASS INSWING SIDE-HINGED DOOR W/SIDELITES, NON-IMPACT APPROVED CONFIGURATIONS FULL LITE PANEL

DRAWN: DWG NO. 08-03315 REV B SCALE NTS DATE 09/27/18 SHEET 3 OF 17

L. ROBERTO LOMAS P.E. 400 S. PALM AVE, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com









DOUBLE W/SIDELITE (MULL)

EXTERIOR VIEW



EXTERIOR VIEW



REVISIONS

DESCRIPTION

REVISED TO ADD INSTALLATION DETAILS

REVISED TO ADD 3/4 LITE PANEL

APPROVED

DATE


02/11/2021 R.L.

03/15/2022 R.L.


EXTERIOR VIEW

SINGLE W/SIDELITE (MULL)
EXTERIOR VIEW

NOTE: ALL APPROVED CONFIGURATIONS ARE SHOWN AS LEFT HAND ACTIVE, RIGHT HAND ACTIVE IS ALSO APPROVED.



SINGLE W/SIDELITE
EXTERIOR VIEW



SINGLE W/SIDELITE (MULL)

EXTERIOR VIEW

NAN YA PLASTICS CORPORATION U.S.A. 8989 NORTH LOOP EAST

HOUSTON, TX 77029


SERIES "SLPS" GLAZED FIBERGLASS INSWING SIDE—HINGED DOOR W/SIDELITES, NON—IMPACT APPROVED CONFIGURATIONS 3/4 LITE PANEL


DRAWN: DWG NO. REV
A.R. 08-03315 B


SCALE NTS DATE 09/27/18 SHEET 4 OF 17

L. ROBERTO LOMAS P.E. 400 S. PALM AVE, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com











	REVISIONS		
REV	DESCRIPTION	DATE	APPROVED
А	REVISED TO ADD 3/4 LITE PANEL	02/11/2021	R.L.
В	REVISED TO ADD INSTALLATION DETAILS	03/15/2022	R.L.




### DOOR INSTALLATION DETAIL WOOD FRAMING OR 2X BUCK INSTALLATION


#### NOTES:

- 1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
- 2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112





REVISIONS			
REV	DESCRIPTION	DATE	APPROVED
А	REVISED TO ADD 3/4 LITE PANEL	02/11/2021	R.L.
В	REVISED TO ADD INSTALLATION DETAILS	03/15/2022	R.L.



### METAL STRUCTURE INSTALLATION


#### NOTES:


- 1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
- 2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112

SIGNED: 03/25/2022










REVISIONS

REV DESCRIPTION DATE APPROVED

A REVISED TO ADD 3/4 LITE PANEL 02/11/2021 R.L.

B REVISED TO ADD INSTALLATION DETAILS 03/15/2022 R.L.



### DOOR INSTALLATION DETAIL CONCRETE/MASONRY INSTALLATION


#### NOTES:

- 1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
- 2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112






Luis R. Lomas P.E. TX No.: 101889 Firm No: F-23130




	REVISIONS		
REV	DESCRIPTION	DATE	APPROVED
А	REVISED TO ADD 3/4 LITE PANEL	02/11/2021	R.L.
В	REVISED TO ADD INSTALLATION DETAILS	03/15/2022	R.L.




### SIDELITE INSTALLATION DETAIL WOOD FRAMING OR 2X BUCK INSTALLATION


#### NOTES:

- 1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
- 2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112






	REVISIONS		
REV	DESCRIPTION	DATE	APPROVED
А	REVISED TO ADD 3/4 LITE PANEL	02/11/2021	R.L.
В	REVISED TO ADD INSTALLATION DETAILS	03/15/2022	R.L.





### SIDELITE INSTALLATION DETAIL METAL STRUCTURE INSTALLATION

#### NOTES:

- 1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
- 2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112








REVISIONS

REV DESCRIPTION DATE APPROVED

A REVISED TO ADD 3/4 LITE PANEL 02/11/2021 R.L.


B REVISED TO ADD INSTALLATION DETAILS 03/15/2022 R.L.




## SIDELITE INSTALLATION DETAIL CONCRETE/MASONRY INSTALLATION

#### NOTES:


- 1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
- 2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112






### **EXTERIOR**

### HEAD KEEPER DETAIL




### **EXTERIOR**


### SILL KEEPER DETAIL




### DEADBOLT KEEPER DETAIL




LATCH KEEPER DETAIL





### HINGE INSTALLATION DETAIL MASONRY/CONCRETE INSTALLATION



WOOD AND METAL INSTALLATION







SIGNED: 03/25/2022


# NAN YA PLASTICS CORPORATION U.S.A. 8989 NORTH LOOP EAST HOUSTON, TX 77029

SERIES "SLPS" GLAZED FIBERGLASS INSWING SIDE-HINGED DOOR W/SIDELITES, NON-IMPACT INSTALLATION DETAILS & COMPONENTS


DRAWN: DWG NO. REV
A.R. 08-03315 B


SCALE NTS DATE 09/27/18 SHEET 15 OF 17


L. ROBERTO LOMAS P.E. 400 S. PALM AVE, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com






















INSWING THRESHOLD ZAIL4565

ALTERNATE





ULTIMATE PUSH BUTTON

ASTRAGAL

ALTERNATE

SIGNED: 03/25/2022

REVISIONS

DATE

02/11/2021 R.L.

03/15/2022 R.L.

APPROVED

DESCRIPTION

REVISED TO ADD INSTALLATION DETAILS

REVISED TO ADD 3/4 LITE PANEL

### NAN YA PLASTICS CORPORATION U.S.A.

8989 NORTH LOOP EAST HOUSTON, TX 77029

SERIES "SLPS" GLAZED FIBERGLASS INSWING SIDE—HINGED DOOR W/SIDELITES, NON—IMPACT COMPONENTS

DRAWN: DWG NO. REV A.R. 08-03315 B

SCALE NTS DATE 09/27/18 SHEET 17 OF 17

L. ROBERTO LOMAS P.E. 400 S. PALM AVE, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com

