REVISIONS					
REV	DESCRIPTION	DATE	APPROVED		
А	REVISED TO ADD 3/4 LITE PANEL	02/11/2021	R.L.		
В	REVISED TO ADD INSTALLATION DETAILS	03/15/2022	R.L.		

NOTES:

- 1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH REQUIREMENTS OF THE 2018 IBC AND 2018 IRC.
- 2. WOOD FRAMING AND MASONRY OPENING TO BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO STRUCTURE. FRAMING AND MASONRY OPENING IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
- 3. WHERE SHIM OR BUCK THICKNESS IS LESS THAN 1-1/2" WINDOW UNITS MUST BE ANCHORED THROUGH THE FRAME IN ACCORDANCE WITH MANUFACTURER'S PUBLISHED INSTALLATION INSTRUCTIONS. ANCHORS SHALL BE SECURELY FASTENED DIRECTLY INTO MASONRY, CONCRETE OR OTHER STRUCTURAL SUBSTRATE MATERIAL.
- 4. WHERE WOOD BUCK THICKNESS IS 1-1/2" OR GREATER, BUCK SHALL BE SECURELY FASTENED TO MASONRY, CONCRETE OR OTHER STRUCTURAL SUBSTRATE. WINDOW UNITS MAY BE ANCHORED THROUGH FRAME TO SECURED WOOD BUCK IN ACCORDANCE WITH MANUFACTURER'S PUBLISHED INSTALLATION INSTRUCTIONS.
- 5. WHERE 1X BUCK IS NOT USED DISSIMILAR MATERIALS MUST BE SEPARATED WITH APPROVED COATING OR MEMBRANE. SELECTION OF COATING OR MEMBRANE IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
- 6. BUCKS SHALL EXTEND BEYOND WINDOW INTERIOR FACE SO THAT FULL FRAME SUPPORT IS PROVIDED.
- 7. SHIM AS REQUIRED AT EACH ANCHOR LOCATION WITH LOAD BEARING SHIM. SHIM WHERE SPACE OF 1/16" OR GREATER OCCURS. MAXIMUM ALLOWABLE SHIM STACK TO BE 1/4".
- 8. SHIMS SHALL BE LOCATED, APPLIED AND MADE FROM MATERIALS AND THICKNESS CAPABLE OF SUSTAINING APPLICABLE LOADS.
- 9. WIND LOAD DURATION FACTOR Cd=1.6 WAS USED FOR WOOD ANCHOR CALCULATIONS.
- 10. FRAME MATERIAL: CO-EXTRUDED PVC FOAM.
- 11. UNITS MUST BE GLAZED PER ASTM E1300, SEE SHEET 17 FOR GLAZING DETAILS.
- 12. APPROVED IMPACT PROTECTIVE SYSTEM <u>IS NOT REQUIRED</u> FOR THIS PRODUCT IN WIND BORNE DEBRIS REGIONS.
- 13. FOR ANCHORING INTO WOOD FRAMING OR 2X BUCK USE #10 WOOD SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/4" MINIMUM EMBEDMENT INTO SUBSTRATE. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.

- 14. FOR ANCHORING INTO MASONRY/CONCRETE USE 3/16" TAPCONS WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/4" MINIMUM EMBEDMENT INTO SUBSTRATE WITH 2" MINIMUM EDGE DISTANCE. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
- 15. FOR ANCHORING INTO METAL STRUCTURE USE #10 SMS OR SELF DRILLING SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE 3 THREADS MINIMUM BEYOND STRUCTURE INTERIOR WALL. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
- 16. ALL FASTENERS TO BE CORROSION RESISTANT.
- 17. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BELOW:
 - A. WOOD MINIMUM SPECIFIC GRAVITY OF G=0.42
 - B. CONCRETE MINIMUM COMPRESSIVE STRENGTH OF 3,192 PSI.
 - C. MASONRY STRENGTH CONFORMANCE TO ASTM C-90, GRADE N, TYPE 1 (OR GREATER).
 - D. METAL STRUCTURE: STEEL 18GA, 33KSI OR ALUMINUM 6063-T5 .125" THICK MINIMUM
- 18. APPROVED CONFIGURATIONS: X, X/O, O/X, OX, XO, OX/O, XO/O, XX, XX/O, O/XX, OXX, XXO, OXX/O AND O/XXO, SEE SHEET 3.
- 19. SIDELITES ARE ASSEMBLED TO FRAME WITH #10 X 3" WOOD SCREWS LOCATED 4" FROM EACH END AND 19 1/8" MAX O.C. THEREAFTER AT JAMBS AND 4" FROM EACH END AND ONE AT MIDSPAN AT HEAD AND SILL.


SIGNED: 03/25/2022


NAN YA PLASTICS CORPORATION U.S.A. 8989 NORTH LOOP EAST HOUSTON, TX 77029 TABLE OF CONTENTS SERIES "SLPS" GLAZED FIBERGLASS INSWING SHEET NO. DESCRIPTION SIDE-HINGED DOOR W/SIDELITES - IMPACT 1 NOTES NOTES 2 ELEVATIONS DRAWN: DWG NO. 08-03313 3 - 4 APPROVED CONFIGURATIONS A.R. SCALE NTS DATE 09/27/18 ANCHORING LAYOUTS OF 17 5 - 6 L. ROBERTO LOMAS P.E. 7 - 15 INSTALLATION DETAILS 400 S. PALM AVE, INDIALANTIC, FL 32903 16 - 17 | COMPONENTS & GLAZING DETAIL 434-688-0609 rllomas@lrlomaspe.com



Luis R. Lomas P.E. TX No.: 101889 Firm No: F-23130


1





SERIES SLPS IN-SWING SIDE-HINGED DOOR W/SIDELITES

EXTERIOR VIEW
FULL LITE PANEL



SERIES SLPS IN-SWING SIDE-HINGED DOOR W/SIDELITES

EXTERIOR VIEW

3/4" LITE PANEL

DESIGN PRESSURE RATING	IMPACT RATING
±40.0PSF	LARGE AND SMALL MISSILE IMPACT

MISSILE LEVEL D, WIND ZONE 4

SIGNED: 03/25/2022

NOTES.

- 1. PANEL SIZE: 35 3/4" X 79 1/4"
- 2. D.L.O.: 25" X 63"

	HARDWARE SCHEDULE
	HANDLE SETS AT ACTIVE PANEL
	STAINLESS STEEL FLUSH BOLT BAR WITH STRIKE PLATES AT PASSIVE PANEL
C.	FLUSH BOLT MECHANISM (DIE CAST, STEEL, POM) AT PASSIVE PANEL
D.	STEEL DEADBOLT WITH KEEPER AT ACTIVE PANEL, AT 38 3/4" FROM FRAME HEAD
E.	STEEL LATCH WITH KEEPER AT ACTIVE PANEL, AT 44 1/4" FROM FRAME HEAD
F.	(3) 4X4 DOOR HINGE AT STILE OF ACTIVE AND PASSIVE PANEL, AT 8 5/8", 40 3/8" AND 72 3/16" FROM FRAME HEAD
G.	T-ASTRAGAL AT ACTIVE AND PASSIVE PANELS
Н.	ALUMINUM REINFORCEMENT (A) AT ASTRAGAL
l.	ALUMINUM MULLION REINFORCEMENT (B) AT INTEGRAL MULLION

NAN YA PLASTICS CORPORATION U.S.A.
8989 NORTH LOOP EAST
HOUSTON, TX 77029


SERIES "SLPS" GLAZED FIBERGLASS INSWING SIDE—HINGED DOOR W/SIDELITES — IMPACT ELEVATIONS


DRAWN: DWG NO. REV
A.R. 08-03313 B

SCALE NTS DATE 09/27/18 SHEET 2 OF 17


L. ROBERTO LOMAS P.E. 400 S. PALM AVE, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com









EXTERIOR VIEW



— 74 3/4" —

- 37 3/8" - 37 3/8" **-**









REVISIONS

DATE

02/11/2021 R.L.

03/15/2022 R.L.

APPROVED

DESCRIPTION

REVISED TO ADD INSTALLATION DETAILS

REVISED TO ADD 3/4 LITE PANEL

NOTE:

82 7/16"

FIXED

ALL APPROVED CONFIGURATIONS ARE SHOWN AS LEFT HAND ACTIVE, RIGHT HAND ACTIVE IS ALSO APPROVED.

ACTIVE

SINGLE W/SIDELITE (MULL)

EXTERIOR VIEW

FIXED

NAN YA PLASTICS CORPORATION U.S.A.
8989 NORTH LOOP EAST
HOUSTON, TX 77029


SERIES "SLPS" GLAZED FIBERGLASS INSWING SIDE-HINGED DOOR W/SIDELITES - IMPACT APPROVED CONFIGURATIONS FULL LITE PANEL

DRAWN: DWG NO. 08-03313 REV B SCALE NTS DATE 09/27/18 SHEET 3 OF 17


L. ROBERTO LOMAS P.E. 400 S. PALM AVE, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com



SIGNED: 03/25/2022




EXTERIOR VIEW





DOUBLE W/SIDELITE (MULL)

EXTERIOR VIEW




REVISIONS			
REV	DESCRIPTION	DATE	APPROVED
А	REVISED TO ADD 3/4 LITE PANEL	02/11/2021	R.L.
В	REVISED TO ADD INSTALLATION DETAILS	03/15/2022	R.L.






EXTERIOR VIEW

NOTE: ALL APPROVED CONFIGURATIONS ARE SHOWN AS LEFT HAND ACTIVE, RIGHT HAND ACTIVE IS ALSO APPROVED.



SINGLE W/SIDELITE EXTERIOR VIEW



SINGLE W/SIDELITE (MULL)

EXTERIOR VIEW

NAN YA PLASTICS CORPORATION U.S.A.
8989 NORTH LOOP EAST
HOUSTON, TX 77029

SERIES "SLPS" GLAZED FIBERGLASS INSWING SIDE-HINGED DOOR W/SIDELITES - IMPACT APPROVED CONFIGURATIONS 3/4 LITE PANEL


DRAWN: A.R. DWG NO. 08-03313 REV B


SCALE NTS DATE 09/27/18 SHEET 4 OF 17


L. ROBERTO LOMAS P.E. 400 S. PALM AVE, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com




SIGNED: 03/25/2022







REV		DESCRIPTION	DATE	APPROVED
	A REVISED TO ADD 3/4 LITE PANEL		02/11/2021	R.L.
	В	REVISED TO ADD INSTALLATION DETAILS	03/15/2022	R.L.





DOOR INSTALLATION DETAIL WOOD FRAMING OR 2X BUCK INSTALLATION

NOTES:


- 1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
- 2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112

SIGNED: 03/25/2022






	REVISIONS				
	REV	DESCRIPTION	DATE	APPROVED	
А		REVISED TO ADD 3/4 LITE PANEL	02/11/2021	R.L.	
	В	REVISED TO ADD INSTALLATION DETAILS	03/15/2022	R.L.	




NOTES:


- 1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
- 2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112

SIGNED: 03/25/2022



METAL STRUCTURE INSTALLATION






REVISIONS

REV DESCRIPTION DATE APPROVED

A REVISED TO ADD 3/4 LITE PANEL 02/11/2021 R.L.


B REVISED TO ADD INSTALLATION DETAILS 03/15/2022 R.L.




NOTES:

- 1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
- 2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112


SIGNED: 03/25/2022



CONCRETE/MASONRY INSTALLATION



REVISIONS					
RI	REV DESCRIPTION A REVISED TO ADD 3/4 LITE PANEL		DATE	APPROVED	
,			02/11/2021	R.L.	
	В	REVISED TO ADD INSTALLATION DETAILS	03/15/2022	R.L.	





SIDELITE INSTALLATION DETAIL WOOD FRAMING OR 2X BUCK INSTALLATION

NOTES:


- 1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
- 2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112

SIGNED: 03/25/2022





REVISIONS					
REV	REV DESCRIPTION A REVISED TO ADD 3/4 LITE PANEL		APPROVED		
А			R.L.		
В	REVISED TO ADD INSTALLATION DETAILS	03/15/2022	R.L.		





SIDELITE INSTALLATION DETAIL METAL STRUCTURE INSTALLATION


NOTES:

- 1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
- 2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112

SIGNED: 03/25/2022








REVISIONS

REV DESCRIPTION DATE APPROVED

A REVISED TO ADD 3/4 LITE PANEL 02/11/2021 R.L.

B REVISED TO ADD INSTALLATION DETAILS 03/15/2022 R.L.



CONCRETE/MASONRY INSTALLATION

NOTES:

- INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.
- 2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112


SIGNED: 03/25/2022






Luis R. Lomas P.E. TX No.: 101889 Firm No: F-23130

1




EXTERIOR

HEAD KEEPER DETAIL




EXTERIOR


SILL KEEPER DETAIL




DEADBOLT KEEPER DETAIL




LATCH KEEPER DETAIL





HINGE INSTALLATION DETAIL MASONRY/CONCRETE INSTALLATION



WOOD AND METAL INSTALLATION







SIGNED: 03/25/2022


NAN YA PLASTICS CORPORATION U.S.A. 8989 NORTH LOOP EAST HOUSTON, TX 77029


SERIES "SLPS" GLAZED FIBERGLASS INSWING SIDE—HINGED DOOR W/SIDELITES — IMPACT INSTALLATION DETAILS & COMPONENTS


DRAWN: DWG NO. REV
A.R. 08-03313 B


SCALE NTS DATE 09/27/18 SHEET 15 OF 17


L. ROBERTO LOMAS P.E. 400 S. PALM AVE, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com




















INSWING THRESHOLD ZAIL4565


ALTERNATE





ULTIMATE PUSH BUTTON
ASTRAGAL
ALTERNATE





SIGNED: 03/25/2022

NAN YA PLASTICS CORPORATION U.S.A. 8989 NORTH LOOP EAST

HOUSTON, TX 77029

SERIES "SLPS" GLAZED FIBERGLASS INSWING SIDE-HINGED DOOR W/SIDELITES - IMPACT COMPONENTS & GLAZING DETAILS

DRAWN:		DWG NO.		REV
A.R.		C	8-03313	В
SCALE NTS	DATE O	9/27/18	SHEET 17 OF 17	

L. ROBERTO LOMAS P.E. 400 S. PALM AVE, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com

