

CLOPAY MODEL 3200, 3220 HOLMES MODEL 240, 240G

REVISIONS REV. NO. ZONE: DATE: ECN NO. APPVD: DESCRIPTION 01 SEE REVISION HISTORY ON SHEET 1

HORIZONTAL (TOP) JAMB (NO LOAD FROM DOOR) **FASTENER** MAX. O.C. - 2x6 VERTICAL JAMB

В

## JAMB TO SUPPORTING STRUCTURE ATTACHMENT

NOTES:


1. ALL THE LOAD FROM THE DOOR IS TRANSFERRED TO THE TRACK AND THEN FROM THE TRACK TO THE 2x6 VERTICAL SYP (GRADE #2 OR BETTER) JAMBS. NO LOAD FROM THE DOOR IS

2. EACH VERTICAL JAMB SEES A MAXIMUM DESIGN LOAD OF +330 LB & -330 LB. PER LINEAR

3. ALL JAMB FASTENERS MAY BE (BUT ARE NOT REQUIRED TO BE) COUNTERSUNK TO PROVIDE A

FLUSH MOUNTING SURFACE.
4. A 1/3 STRESS INCREASE FOR WIND LOAD WAS NOT USED IN THE CALCULATION OF ALLOWABLE LOADS FOR ANCHORS AND FASTENERS FOR STEEL, CONCRETE AND MASONRY.

NOTE: 2x6 WOOD JAMBS ARE NOT REQUIRED WITH CONTINUOUS ANGLE MOUNT TRACK, HOWEVER, IF DESIRED ON STEEL JAMBS OR CONCRETE OR BLOCK WALLS, APPROVED FASTENERS AS DETAILED BELOW SHOULD BE INCREASED IN LENGTH BY 1-1/2" AND INSTALLED DIRECTLY THROUGH THE ANGLE AND 2×6 WOOD JAMBS INTO THE STEEL JAMBS OR CONCRETE OR BLOCK WALLS. ANCHORS CAN BE (BUT ARE NOT REQUIRED TO BE) COUNTERSUNK TO PROVIDE A FLUSH MOUNTING SURFACE. CONTINUOUS ANGLE TRACK CAN BE ANCHORED DIRECTLY TO GROUT REINFORCED BLOCK WALL OR 3,000 PSI MIN. CONCRETE COLUMN OR STEEL JAMBS.



FASTENER ATTACHMENT TO SUPPORTING STRUCTURE SCHEDULES

		MAXIMUM	
		ON-CENTER	
		DISTANCE	STEEL
DUN BING TOPE	FLOTENIER THOSE		WASHERS
BUILDING TYPE	FASTENER TYPE	FASTENERS*	REQUIRED
HOLLOW BLOCK WALL	1/4" x 1-1/4" MIN. EMBED ULTRACON CONCRETE ANCHOR	5"	1" O.D.
GROUT FILLED BLOCK WALL	1/4" x 1-3/4" MIN. EMBED ULTRACON CONCRETE ANCHOR	8-1/4"	1" O.D.
2000 PSI MIN. CONCRETE	1/4" x 1" MIN. EMBED ULTRACON CONCRETE ANCHOR	7-1/4"	1" O.D.
2000 PSI MIN. CONCRETE	1/4" x 1" MIN. EMBED TAPCON CONCRETE ANCHOR	6-3/4"	1" O.D.
2000 PSI MIN. CONCRETE	3/8" x 1-3/4" MIN. EMBED WEJ-IT ANKR TITE SLEEVE ANCHOR	15"	INCLUDED
4000 PSI MIN. CONCRETE	3/8" x 1-3/4" MIN. EMBED WEJ-IT ANKR TITE SLEEVE ANCHOR	24"	INCLUDED
WOOD FRAME (SYP 0.55 SG)	1/2" x 3" LAG SCREW (ASTM A307, GRADE A) 1-5/8" EMBED INTO STRUCTURE	16-1/2"	1" O.D.
14GA STEEL (0.060" MIN.)	1/4"-14 x 1" ITW BUILDEX TEKS SELF-DRILLING FASTENER	6-3/4"	1" O.D.
12GA STEEL (0.105" MIN.)	1/4"-14 x 1" ITW BUILDEX TEKS SELF-DRILLING FASTENER	12"	1" O.D.
1/8" STEEL	1/4"-14 x 1" ITW BUILDEX TEKS SELF-DRILLING FASTENER	14-1/2"	1" O.D.

FIRST (BOTTOM) ANCHOR STARTING AT NO MORE THAN HALF OF THE MAXIMUM ON-CENTER DISTANCE. HIGHEST ANCHOR INSTALLED AT LEAST AS HIGH AS THE DOOR OPENING.

CLOPAY DOES NOT SUPPLY JAMB ATTACHMENT FASTENERS.

MINIMUM DISTANCE BETWEEN CENTER OF ANCHOR AND EDGE OF CONCRETE BLOCK: 2-1/2", EXCLUDING STUCCO THICKNESS.

SECTION A-A (SIDE VIEW) DESIGN LOADS: +30.0, -30.0 PSF

MANUFACTURING PRODUCT CODE: MPC: C-DSIE-1F447 TEST LOADS: +45.0, -45.0 PSF PART NO.: N/A 8585 Duke Boulevard Mason, OH 45040 USA Tel. No. 513-770-4800 Clopay CLOPAY WINDLOAD RATING

TOLERANCES are  $.0 = \pm .031$  $.00 = \pm .015$  $.000 = \pm .005$  $.0000 = \pm .001$ Degrees =  $\pm 1/2^{\circ}$ 

Unless Stated Otherwise

CORPORATION DRAWN BY: RJH

DESCRIPTION: MODEL 240/3200/3220 WINDLOAD 22'-2" DATE: 2/7/17 | SCALE: NTS DWG. T SIZE D DATE: -SHEET 2 OF 4

В

CHECKED BY: -Unless Stated Otherwise
DIMENSIONS ARE IN INCHES. DWG. NO.: 105054 VER: TDI

MARK WESTERSIELD, P.E. FLORIDA P.E. #48495. NC P.E. #23832, TEXAS P.E. #91513

2

