



SUPERIMPOSED LOAD DIAGRAM

## GENERAL NOTES:

- 1. THIS DOOR EVALUATED IN ACCORDANCE WITH TEST METHODS ASTM E330-02 AND ANSI/DASMA 108.
- 2. THIS PRODUCT EVALUATION IS GENERIC. IT DOES NOT INCLUDE INFORMATION PREPARED FOR A SPECIFIC SITE.
- 3. IT IS THE RESPONSIBILITY OF OTHER, TO VERIFY THE STRUCTURAL CAPACITY OF THE SUBSTRATE (JAMB) TO RESIST THE LOADS IMPOSED BY THE ROLL-UP DOOR.
- 4. ALL DOOR JAMBS (MASONRY OR STEEL) MUST BE DESIGNED TO RESIST THE FORCES IN SUPERIMPOSED LOAD DIAGRAM.
- 5. THE DOOR ASSEMBLY SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS INSTALLATION INSTRUCTIONS.
- 6. COMPLIES WITH IBC/IRC 2018.
- 7. PROFESSIONAL ENGINEER'S SEAL PROVIDED ONLY FOR VERIFICATION OF WINDLOAD CONSTRUCTION DETAIL.

PRESSURE DOOR WIDTH (PSF) +43.7</= 10'-0''-50.0+39.9 11'-0" -45.7+36.8 12'-0" -42.1+34.1 13'-0" -39.0+31.7 14'-0" -36.3+29.7 15'-0" -34.0+28.0 16'-0" -32.0+25.4 17'-0" -29.1+23.2 18'-0" -26.6 +21.3 19'-0" -24.4+19.7 20'-0" -22.6

DOOR SCHEDULE

DESIGN

ART NUMBER: THESE CONFIDENTIAL DOCUMENTS SUBMITTED BY DBCI CONTAIN INFORMATION OF A PROPRIETARY NATURE AND MAY NOT BE REPRODUCED OR USED TO MANUFACTURE ANYTHING IN PART OR IN WHOLE FOR ANY PURPOSE OTHER THAN THAT WHICH IS NECESSARY FOR PREPARATION OF BIDS OR ENGINEERING WITHOUT THE EXPRESS PERMISSION OF DBCI WHICH MAY RECALL DOCUMENTS AT ANY TIME. N/A ATERIAL: N/A PLIED FINISH N/A UNIT OF MEASURE DATE: BRAY ALLEN 1/14/08 CHECKED 11/14/08 **B** BRAY ALLEN

DOORS & BUILDING COMPONENTS DOUGLASVILLE, GA CHANDLER, AZ HOUSTON, 1 ©2000 DBCI ALL RIGHTS RESERVED

26 GA. WIND LOAD, MAX. SIZE 20'-0" × 20'-0"

5000 DAAR ASSEMBLY

 $\supset$ NONE

SIGNATURE MUST BE VERIFIED ON ANY **ELECTRONIC COPIES.** 

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE

JOHN E. SCATES, P.E.

2560 King Arthur Blvd, Ste 124-54

Lewisville, TX 75056

FL PE 51737

TX PE 56308/F-2203