




John E. Scates 2560 King Arthur Blvd, Ste 124-54 Lewisville TX 75056 TX PE #56308-f2203



352 lbs. allowable load per fastener

Track Assembly Attachment

to Wood Back Jamb 2" Track Angle Mount Turned-in (shown) 3" Track Angle Mount Available

Hex Head Lag Screw 5/16" x 1-3/4" with 5/16" flat washer 18" O.C. 352 lbs. allowable load per fastener

Track Assembly Attachment to Wood Back Jamb 2" Track Angle Mount Turned-out (shown)

3" Track Angle Mount Available


2x0 Attachment to Structure						
Structure Type	Fastener Type	Minimum Embedment	Minimum Edge Distance	Minimum on Center Spacing	Maximum on Center Spacing	Allowable Tension Load
2500 PSI Min. Concrete	1/4" Tapcon+ (Plus) with 1-1/8' OD Washer	2"	2.5	6"	24"	526
Southern Pine	3/8" x 3" Lag with 1-1/8" OD Washer	1.50"	1.50"	1.50"	24"	655
Spruce Pine Fir	3/8" x 3" LAG with 1-1/8" OD Washer	1.50"	1.50"	1.50"	24"	482


Scale: None Drawn by: R. Frey RAYNOR Checked by: G. Wedekind Date: 01/29/19 1101 Fast River Road ECO: 7679.01

Spec, Wind Load TH160, TM175, TM200

P-2812 В

Professional Engineer's seal provided only for verification of wind load construction details





ECO: 7679.01

P-2812

В

3

Professional Engineer's seal provided only for verification of wind load construction details

John E. Scates 2560 King Arthur Blvd, Ste 124-54 Lewisville, TX 75056 FL PE #51737

TX PE #56308-f2203