





John E. Scates 2560 King Arthur Blvd, Ste 124-54 Lewisville TX 75056 TX PE #56308-f2203



See iamb attachment detail for anchorage requirements

> Track Assembly Attachment to Wood Back Jamb 2" Track Angle Mount Turned-in (shown) 3" Track Angle Mount Available



Track Assembly Attachment to Wood Back Jamb 2" Track Angle Mount Turned-out (shown) 3" Track Angle Mount Available

Structure Type	Fastener Type	Minimum Embedment	Minimum Edge Distance	Minimum on Center Spacing	Maximum on Center Spacing	Allowable Tension Load
2500 PSI Min. Concrete	1/4" Tapcon+ (Plus) with 1-1/8' OD Washer	2"	2.5	6"	24"	526
Southern Pine	3/8" x 3" Lag with 1-1/8" OD Washer	1.50"	1.50"	1.50"	24"	655
Spruce Pine Fir	3/8" x 3" LAG with 1-1/8" OD Washer	1.50"	1.50"	1.50"	24"	482

Scale: None Drawn by: R. Frey RAYNOR Checked by: G. Wedekind Date: 02/05/19 1101 Fast River Road ECO: 7679.01

Spec, Wind Load SteelForm - S24C, S24, S20

P-2818 В 2

Professional Engineer's seal provided only for verification of wind load construction details

