



- 1. IMPACT RESISTANT GLAZING OPTION (SEE PAGE 3) - 1/4" IMPACT RESISTANT POLYCARBONATE IN ALUMINUM FRAMES SCREWED TOGETHER WITH DIMENSIONS SHOWN IN TABLE, INSTALLED IN TOP OR INTERMIEDIATE SECTION (WITH OR WITHOUT DECORATIVE INSERT) MEETS UNIFORM STATIC WIND PRESSURES SHOWN ON THIS DRAWING. GLAZING IS IMPACT RESISTANT AND MEETS THE REQUIREMENTS FOR WIND-BORNE DEBRIS
- 2. NON-IMPACT RESISTANT GLAZING OPTION (SEE PAGE 3) - .090" MINIMUM SSB ANNEALED GLAZING IN MOLDED FRAMES SCREWED TOGETHER WITH DIMENSIONS SHOWN IN TABLE, INSTALLED IN TOP OR INTERMEDIATE SECTION (WITH OR WITHOUT DECORATIVE INSERTS) MEETS UNIFORM STATIC WIND PRESSURES SHOWN ON THIS DRAWING. GLAZING IS NOT IMPACT RESISTANT AND DOES NOT MEET THE REQUIREMENTS FOR WIND-BORNE DEBRIS REGIONS.
- 3. VINYL OR WOOD DOOR STOP NAILED A MAXIMUM OF 6" O.C. MUST OVERLAP TOP AND BOTH ENDS OF PANELS MINIMUM 7/16" TO MEET NEGATIVE PRESSURES.
- 4. KEY LOCK, SLIDE LOCK, OR OPERATOR REQUIRED.
- 5. FACER STEEL TO HAVE A MINIMUM 29 GA THICKNESS AND BACKER STEEL TO HAVE A MINIMUM 29 GA THICKNESS.
- 6. EACH SECTION HAS AN INTERNAL 1" WIDE X 20 GA CONTINUOUS STEEL STRIP AT THE TOP AND BOTTOM OF THE SECTION.
- 7. THE DESIGN OF THE SUPPORTING STRUCTURAL ELEMENTS SHALL BE THE RESPONSIBILITY OF THE PROFESSIONAL OF RECORD FOR THE BUILDING OR STRUCTURE AND IN ACCORDANCE WITH CURRENT BUILDING CODES FOR THE LOADS LISTED ON THIS
- 8. DOOR JAMB TO BE MINIMUM 2x6 STRUCTURAL GRADE LUMBER. REFER TO JAMB CONNECTION SUPPLEMENT FOR ATTACHMENT TO SUPPORTING
- 9. FOR LOW HEAD ROOM LIFT CONDITIONS, TOP BRACKET SHALL BE A 13 GA LHR 7/4 TOP BRACKET WITH A MINIMUM OF (3) 1/4-20x3/4" SELF DRILLING CRIMPTITE SCREWS IN LIEU OF THE BRACKET SHOWN ON THIS DRAWING. U-BAR ON TOP SECTION SHALL BE INSTALLED ON TOP OF LHR TOP BRACKETS.





SUP	ER	MP	OSED	<b>DESIGN</b>	PRESSURE
OAD	S	ON	SUPP	ORTING	STRUCTURE

DOOR WIDTH	DOOR HEIGHT	UNIFORM LOAD EACH JAMB (PLF)		
8'-2"	ALL	+145.8/-167.4		
9'-2" ALL		+163.6/-187.9		



DWAYNE J. KORNISH, PE 4576 COUNTY ROAD 160 MOUNT HOPE, OHIO FL PE 77945

PROFESSIONAL ENGINEER'S SEAL PROVIDED ONLY FOR VERIFICATION OF WINDLOAD CONSTRUCTION DETAILS.

JAMB BRACKET SCHEDULE									
DOOR HEIGHT	I NO OF I	NO. OF JAMB BRACKETS (EACH JAMB)	LOCATION OF CENTERLINE OF JAMB BRACKETS MEASURED FROM BOTTOM OF TRACK (ALL DIMENSIONS ± 2")						
6'-6"	4	7	2" (JB-US), 10" (JB-US), 21-3/4" (JB-US), 29-3/4" (JB-US), 39" (JB-US), 48" (JB-US), 57-1/4" (JB-US)						
7'-0"	4	7	2" (JB-US), 10" (JB-US), 21-3/4" (JB-US), 29-3/4" (JB-US), 42" (JB-US), 52-1/2" (JB-US), 63-1/4" (JB-US)						
7'-6"	4 OR 5	8	2" (JB-US), 10" (JB-US), 18-3/4" (JB-US), 26-3/4" (JB-US), 36" (JB-US), 45" (JB-US), 54-1/4" (JB-US), 74-1/2" (JB-US)						
8'-0"	4 OR 5	8	2" (JB-US), 10" (JB-US), 21-3/4" (JB-US), 29-3/4" (JB-US), 39" (JB-US), 48" (JB-US), 57-1/2" (JB-US), 75-1/2" (JB-US)						
> 8'−0"			SEE NOTE BELOW						

(JB-US) FOLLOWING DIMENSION DENOTES SLOTTED JAMB BRACKET ATTACHED TO TRACK WITH 1/4-20x9/16" TRACK BOLT AND NUT AS SHOWN ABOVE.

ALL DOORS GREATER THAN 8' IN HEIGHT REQUIRE USE OF CONTINUOUS WALL ANGLE. SEE SUPPLEMENT TRACK CHART FOR DETAILS.

COMPLIES WITH THE REQUIREMENTS OF IBC/IRC 2018.

APPROVED SIZES



DESIGN (PSF): +35.70/-41.00 MAX WIDTH: 9'-2' +53.55/-61.50 MAX HEIGHT: 24'-0" IMPACT/CYCLIC RATED (YES/NO): YES MAX SECTION HEIGHT: 24" CHECKEL MODELS 190/490/160/593/594/591/592/596/599/5740/5760/7560

DIVISION OF OVERHEAD DOOR COR 3395 ADDISON DRIVE PENSACOLA, FLORIDA 32514 WINDLOAD SPECIFICATION OPTION CODE 2204 (850) 474-9890

STATIC PRESSURE RATINGS

TLC SHEET 1 OF DRAWING PART NO. REV. 411706 В

DATE

5/13/20

SIZE: A

NAME

SW

SCALE: N.T.S.

DRAWN

REVISIONS

P1 REVISED MODELS PER

DRAWING TO SHOW GLAZING CROSS-SECTION

REV B - UPDATED PER


REV A - UPDATED


TLC 3/30/21

PCR 32769


SW 2/16/22


WL008 SW 9/14/2020





	OUTSIDE FRAME SIZE	DAYLIGHT OPENING (DLO)	SCREW QTY EA HORIZ LEG	SCREW QTY EA VERT LEGS	SCREW QTY TOTAL	DETAIL
	17"X51"	14X48	5	3	16	G
	15.1X44"	11.5"X40.5"	8	3	22	Н
	14.9X20.8"	11"X17"	3	3	12	Н
- [	7"X40.8	4"X37.8"	5	2	14	Н
	15.3"X44.1"	11.3"X40.1"	6	3	18	1
ı	14.6"X20.8"	10.6"X16.8"	3	2	10	1
	13"X38"	9"X34"	5	2	14	ı





The Genuine. The Original.

OVERHEAD DOOR

STATIC PRESSURE RATINGS APPROVED SIZES SCALE: N.T.S. SIZE: A DESIGN (PSF): +35.70/-41.00 MAX WIDTH: DATE NAME +53.55/-61.50 MAX HEIGHT: 24'-0" 5/13/20 SW TEST (PSF): DRAWN IMPACT/CYCLIC RATED (YES/NO): YES MAX SECTION HEIGHT: 24" CHECKED 3/30/21 TLC SHEET 3 OF MODELS 190/490/160/593/594/591/592/596/599/5740/5760/7560

DIVISION OF OVERHEAD DOOR CORP 3395 ADDISON DRIVE PENSACOLA, FLORIDA 32514 (850) 474-9890

WINDLOAD SPECIFICATION OPTION CODE 2204

DRAWING PART NO. | REV. | 204 | 411706 | B

**REVISIONS**