

. IMPACT RESISTANT GLAZING OPTION (SEE PAGE 3) -1/4" IMPACT RESISTANT POLYCARBONATE IN ALUMINUM FRAMES SCREWED TOGETHER WITH DIMENSIONS SHOWN IN TABLE, INSTALLED IN TOP OR INTERMIEDIATE SECTION (WITH OR WITHOUT DECORATIVE INSERT) MEETS UNIFORM STATIC WIND PRESSURES SHOWN ON THIS DRAWING. GLAZING IS IMPACT RESISTANT AND MEETS THE REQUIREMENTS FOR WIND-BORNE DEBRIS REGIONS.

2. VINYL OR WOOD DOOR STOP NAILED A MAXIMUM OF 6" O.C. MUST OVERLAP TOP AND BOTH ENDS OF PANELS MINIMUM 7/16" TO MEET NEGATIVE PRESSURES.

3. KEY LOCK, SLIDE LOCK, OR OPERATOR REQUIRED.


4. FACER STEEL TO HAVE A MINIMUM 29 GA THICKNESS AND BACKER STEEL TO HAVE A MINIMUM 29 GA


5. EACH SECTION HAS AN INTERNAL 1"WIDE X 20 GA CONTINUOUS STEEL STRIP AT THE TOP AND BOTTOM OF

6. THE DESIGN OF THE SUPPORTING STRUCTURAL ELEMENTS SHALL BE THE RESPONSIBILITY OF THE PROFESSIONAL OF RECORD FOR THE BUILDING OR STRUCTURE AND IN ACCORDANCE WITH CURRENT BUILDING CODES FOR THE LOADS LISTED ON THIS DRAWING.

7. DOOR JAMB TO BE MINIMUM 2x6 STRUCTURAL GRADE LUMBER. REFER TO JAMB CONNECTION SUPPLEMENT FOR ATTACHMENT TO SUPPORTING STRUCTURE.

8. FOR LOW HEAD ROOM LIFT CONDITIONS, TOP BRACKET SHALL BE A 13 GA LHR 7/4 TOP BRACKET WITH A MINIMUM OF (3) 1/4-20x3/4" SELF DRILLING CRIMPTITE SCREWS IN LIEU OF THE BRACKET SHOWN ON THIS DRAWING. U-BAR ON TOP SECTION SHALL BE INSTALLED ON TOP OF LHR TOP BRACKETS.





REVISIONS

P1 REVISED MODELS PER

SW 9/14/2020

REV A - UPDATED DRAWING TO SHOW GLAZING CROSS-SECTION TLC 3/30/21

REV B - UPDATED PER PCR 32769 SW 2/16/22

## SUPERIMPOSED DESIGN PRESSURE LOADS ON SUPPORTING STRUCTURE

ı	LUAL	3 ON	SUFFURTING STRUCTURE					
	DOOR WIDTH	DOOR HEIGHT	UNIFORM LOAD EACH JAMB (PLF)					
ı	8'-2"	ALL	+261.3/-294.0					
ı	9'-2"	ALL	+293.3/-330.0					

NO. OF NO. OF JAMB DOOR HEIGHT SECTIONS (EACH JAMB) 2" (JB-US), 10" (JB-US), 21-3/4" (JB-US), 29-3/4" (JB-US), 39" (JB-US), 48" (JB-US), 57-1/4" (JB-US)

2" (JB-US), 10" (JB-US), 21-3/4" (JB-US), 29-3/4" (JB-US), 42" (JB-US), 52-1/2" (JB-US), 63-1/4" (JB-US)

2" (JB-US), 10" (JB-US), 18-3/4" (JB-US), 26-3/4" (JB-US), 36" (JB-US), 45" (JB-US), 54-1/4" (JB-US), 74-1/2" (JB-US)

2" (JB-US), 10" (JB-US), 21-3/4" (JB-US), 29-3/4" (JB-US), 39" (JB-US), 48" (JB-US), 57-1/2" (JB-US), 75-1/2" (JB-US) 7'-0" 4 7'-6" 4 OR 5 8'-0" 4 OR 5 SEE NOTE BELOW

(JB-US) FOLLOWING DIMENSION DENOTES SLOTTED JAMB BRACKET ATTACHED TO TRACK WITH 1/4-20x9/16" TRACK BOLT AND NUT AS SHOWN ABOVE.

ALL DOORS GREATER THAN 8' IN HEIGHT REQUIRE USE OF CONTINUOUS WALL ANGLE, SEE SUPPLEMENT TRACK CHART FOR DETAILS.

-0333388B OF TEXAS DWAYNE J KORNISH SS/ONAL E

DWAYNE J. KORNISH, PE 3///2022 4576 COUNTY ROAD 160 MOUNT HOPE OLIVA MOUNT HOPE, OHIO FL PE 77945 TX PE 117868

PROFESSIONAL ENGINEER'S SEAL PROVIDED ONLY FOR VERIFICATION OF WINDLOAD CONSTRUCTION DETAILS.

The Genuine. The Original

LOCATION OF CENTERLINE OF JAMB

BRACKETS MEASURED FROM BOTTOM

OF TRACK (ALL DIMENSIONS ± 2")

DIVISION OF OVE PENSACOLA, FLORIDA 32514 (850) 474-9890

	STATIC PE	RESSURE RATINGS		APPROVE	D SIZES	SCALE: N.	T.S.	SIZE:	4
	DESIGN (PSF):	+64.00/-72.00	MAX	WIDTH:	9'-2"		DATE	NAME	
7	TEST (PSF):	+96.00/-108.00	MAX	HEIGHT:	24'-0"	DRAWN	5/19/20	SW	
	IMPACT/CYCLIC	RATED (YES/NO): YES	MAX	SECTION	HEIGHT: 24"	CHECKED	3/30/21	TLC	
MODELS 190/490/160/593/594/591/592/596/599/5740/5760/7560 SHEET 1 OF 3									

COMPLIES WITH THE REQUIREMENTS OF IBC/IRC 2018.


WINDLOAD SPECIFICATION OPTION CODE 2207

PART NO. 411709

REV.


В

	IMPACT/CYCLIC	RATED (YES/NO):	YES MA	X SECTION HEI	GHT: 24" CI	HECKED	3/30
	MODELS 190/49	90/160/593/594/	591/592/	596/599/5740	/5760/75	60	SHEET
ERHEAD DOOR COR							AWING I
JISON DRIVE	I WINDI OVE	CDECIEICAT	TON OF	TION COD	E 2207	7	444



	R	E,	۷l	S	0	NS
--	---	----	----	---	---	----

	IMPACT FRAME SIZE	DAYLIGHT OPENING (DLO)	SCREW QTY EA HORIZ LEG	SCREW QTY EA VERT LEGS	SCREW QTY TOTAL	DETAIL
L	15.3"X44.1" 11.3"X40.1"		6	3	18	Н
	14.6"X20.8"	10.6"X16.8"	3	2	10	Н
	13"X38"	9"X34"	5	2	14	Н





DWAYNE J. KORNISH, PE 4576 COUNTY ROAD 160 MOUNT HOPE, OHIO FL PE 77945 TX PE 117868

PROFESSIONAL ENGINEER'S SEAL PROVIDED ONLY FOR VERIFICATION OF WINDLOAD CONSTRUCTION DETAILS.

The Genuine. The Original.



A DIVISION OF OVERHEAD DOOR CORP 3395 ADDISON DRIVE PENSACOLA, FLORIDA 32514 (850) 474—9890

٠	STATIC PRESSURE RATINGS			APPROVED SIZES			SCALE: N.T.S.	
	DESIGN (PSF):	+64.00/-72.00	MAX	WIDTH:	9'-2"		DATE	NAME
7	TEST (PSF):	+96.00/-108.00	MAX	HEIGHT:	24'-0"	DRAWN	5/19/20	SW
	IMPACT/CYCLIC	RATED (YES/NO): YES	MAX	SECTION	HEIGHT: 24"	CHECKED	3/30/21	TLC
MODELS 190/490/160/593/594/591/592/596/599/5740/5760/7560 SHEET 3 OF						F 3		

MODELS 190/490/160/593/594/591/592/596/599/5740/5760/7560

WINDLOAD SPECIFICATION OPTION CODE 2207

DRAWING PART NO. REV. 411709 В