NOTES: 1. NON-IMPACT RESISTANT GLAZING OPTION -3/32" MINIMUM SSB GLAZING IN MOLDED FRAMES SCREWED TOGETHER WITH A MINIMUM OF (14) #8x1" SCREWS (2X ALONG THE HORIZONTAL AND 5X ALONG THE VERTICAL) INSTALLED IN ANY OR ALL SECTIONS MEETS UNIFORM STATIC WIND PRESSURES SHOWN ON THIS DRAWING. MAXIMUM GLAZING DIMENSIONS SHALL BE 38.5" x 13" CUTOUT. GLASS IS NOT IMPACT RESISTANT AND DOES NOT MEET THE REQUIREMENTS FOR WIND-BORNE DEBRIS REGIONS. SEE DETAIL G, H ON SHEET 3 FOR ASSEMBLY DETAILS. ALTERNATE OPTION- 1/2" DSB ANNEALED GLAZING IN ALUMINUM EXTERIOR FRAME/PLASTIC MOLDED INTERIOR FRAME SCREWED TOGETHER WITH A MINIMUM OF (14) #8X1" SCREWS (2X ALONG THE HORIZONTAL AND 5X ALONG THE HORIZONATAL) INSTALLED IN ANY OR ALL SECTIONS MEETS UNIFORM STATIC WIND PRESSURES SHOWN ON THIS DRAWING. MAXIMUM GLAZING DIMENSIONS SHALL BE 39" X 5-1/6" CUTOUT. GLASS IS NOT IMPACT RESISTANT AND DOES NOT MEET THE REQUIREMENTS FOR WIND-BORNE DEBRIS REGIONS. DLO = 4"X37.8".

- 2. VNYL OR WOOD DOOR STOP NAILED A MAXIMUM OF 6" O.C. MUST OVERLAP TOP AND BOTH ENDS OF PANELS MINIMUM 7/16" TO MEET NEGATIVE PRESSURES.
- 3. KEY LOCK, SLIDE LOCK, OR OPERATOR REQUIRED.
- 4. FACER STEEL TO HAVE A MINIMUM 29 GA THICKNESS AND BACKER STEEL TO HAVE A MINIMUM 29 GA THICKNESS
- 5. EACH SECTION HAS AN INTERNAL 1" WIDE X 20 GA CONTINUOUS STEEL STRIP AT THE TOP AND BOTTOM OF THE SECTION.
- 6. THE DESIGN OF THE SUPPORTING STRUCTURAL ELEMENTS SHALL BE THE RESPONSIBILITY OF THE PROFESSIONAL OF RECORD FOR THE BUILDING OR STRUCTURE AND IN ACCORDANCE WITH CURRENT BUILDING CODES FOR THE LOADS LISTED ON THIS DRAWING.
- 7. DOOR JAMB TO BE MINIMUM 2x6 SOUTHERN PINE LUMBER. REFER TO JAMB CONNECTION SUPPLEMENT FOR ATTACHMENT TO SUPPORTING STRUCTURE.
- 8. FOR LOW HEAD ROOM LIFT CONDITIONS, TOP BRACKET SHALL BE A 13 GA LHR 7/4 TOP BRACKET WITH A MINIMUM OF (3) 1/4-14x7/8" SELF DRILLING CRIMPTITE SCREWS IN LIEU OF THE BRACKET SHOWN ON THIS DRAWNG. U-BAR ON TOP SECTION SHALL BE INSTALLED ON TOP OF LHR TOP BRACKETS.
- 9. COMPLIES WITH THE REQUIREMENTS OF IBC/IRC 2018.

SUPERIMPOSED DESIGN PRESSURE LOADS ON SUPPORTING STRUCTURE								
DOOR WIDTH	DOOR HEIGHT	UNIFORM LOAD EACH JAMB (PLF)						
10'-2"	ALL	+93.6/-105.8						
12'-2"	ALL	+112.0/-126.6						
14'-2"	ALL	+130.4/-147.4						
15'-2"	ALL	+139.6/-157.8						
16'-2"	' ALL +148.8/-168.2							

DWAYNE J KORNISH

TO 117868

ONAL EN

S/20/201 DWAYNE J. KORNISH, PE

4578 COUNTY ROAD 160

MOUNT HOPE, OHIO

FL. PE 77945

TX PE 117868

PROFESSIONAL ENGINEER'S SEAL PROVIDED ONLY FOR VERIFICATION OF WINDLOAD CONSTRUCTION DETAILS.

13 GA HORIZ ANGLE -OVERLAP REQUIRED EXTERNAL BACKUP PLATES TOP ONLY 13 GA FLAG ANGLE -ALIGNED WITH CENTER HINGES 16 GA MIN HORIZ SHEET 5/16x1-5/8" LAG SCREW (MIN 3 AS SHOWN) SHEET (4) 1/4-20x9/16" LARGE HEAD TRACK BOLTS OR 1/4-20 STUDS WITH В 1/4-20 HEX NUTS SHEET 2 16 GA MIN VERT TRACK 1/4-20x9/16" TRACK-BOLT AND 1/4-20 HEX NUT AT EACH JB-US JAMB BRACKET LOCATION С SHEET 2 5/16x1-5/8" LAG GA END STILE SCREW AT EACH JAMB BRACKET 15 GA STIFFENED JAMB-BRACKETS SEE SCHEDULE FOR QUANTITY, LOCATION, AND TYPE KEY LOCK OR SLIDE LOCK EACH END (NOT REQUIRED WITH OPERATOR - SEE NOTE 3). SLIDE LOCK SHOWN FOR CLARITY SHEET D NOTE: (4) SECTION SOLID DOOR SHOWN. SEE NOTES 1 & 2 THIS SHEET FOR SHFFT EXTERNAL BACKUP PLATES BOTTOM ONLY-ALIGNED WITH CENTER

	JAMB BRACKET SCHEDULE									
DOOR HEIGHT	INO OF I	NO. OF JAMB BRACKETS (EACH JAMB)	LOCATION OF CENTERLINE OF JAMB BRACKETS MEASURED FROM BOTTOM OF TRACK (ALL DIMENSIONS ± 2")							
6'-6"	4	4	2" (JB-US), 21-3/4" (JB-US), 48" (JB-US), 57-1/4" (JB-US)							
7'-0"	4	4	2" (JB-US), 21-3/4" (JB-US), 42" (JB-US), 63-1/4" (JB-US)							
7'-6"	4 OR 5	4	2" (JB-US), 26-3/4" (JB-US), 45" (JB-US), 74-1/2" (JB-US)							
8'-0"	4 OR 5	4	2" (JB-US), 21-3/4" (JB-US), 48" (JB-US), 75-1/2" (JB-US)							
> 8'-0"			SEE NOTE BELOW							

(JB-US) FOLLOWING DIMENSION DENOTES SLOTTED JAMB BRACKET ATTACHED TO TRACK WITH 1/4-20x9/16" TRACK BOLT AND NUT AS SHOWN ABOVE.

ALL DOORS GREATER THAN 8' IN HEIGHT REQUIRE USE OF CONTINUOUS WALL ANGLE. SEE SUPPLEMENT TRACK CHART FOR DETAILS.


The Genuine. The Original.	Sī
TERHEAD DOO	DESIGN
O	TEST (P
•	IMPACT/
A DIVISION OF OVERHEAD DOOR CORP 3395 ADDISON DRIVE PENSACOLA, FLORIDA 32514 (850) 474–9890	WIND


al.	STATIC PRESSURE RATINGS		APPROVED SIZES			SCALE: N.T.S.		SIZE:	Α		
	DESIGN (PSF):	+18.40/-20.80	MAX	MDTH:	16'-2"			DATE	N.	AME	
	TEST (PSF):	+27.60/-31.20	MAX	HEIGHT:	24'-0"	DRAW	N	03/23/21	!	SW	
-	IMPACT/CYCLIC	RATED (YES/NO): NO	MAX	SECTION	HEIGHT: 24"	CHEC	KED	****			
	MODELS 5740/5760/190/490/7560/591-596/599						SHEET 1 OF 3				
RP			-	-	-	[DRAV	MNG PART	NO.	REV	
	WINDLOAD	SPECIFICATION	Ob.	OPTION CODE 2608		8		411828	28		
							1		- 1		

REVISIONS

- RELEASE DRAWING

SW 3/23/2021





The Genuine. The Original.

	OUTSIDE FRAME SIZE	DAYLIGHT OPENING (DLO)	SCREW QTY EA HORIZ LEG	SCREW QTY EA VERT LEGS	SCREW QTY TOTAL	DETAIL
	17"X51"	14X48	5	3	16	G
ı	15.1X44"	11.5"X40.5"	8	3	22	Н
	14.9X20.8"	11"X17"	3	3	12	Н
	7"X40.8	4"X37.8"	5	2	14	Н

DWAYNE J KORNISH

DWAYNE J KORNISH

DWAYNE J. KORNISH, PE

4578 COUNTY ROAD 160

MOUNT HOPE

FL PE 77945

TX PE 117868

PROFESSIONAL ENGINEER'S SEAL PROVIDED ONLY FOR VERIFICATION OF WINDLOAD CONSTRUCTION DETAILS.

9							
A TOHEAD DO	DESIGN (PSF):	+18.40/-20.80	MAX WIDTH:	16'-2 "			
OVERHEAD DOOR	TEST (PSF):	+27.60/-31.20	MAX HEIGHT	: 24'-0"	DRAW	N	
•	IMPACT/CYCLIC	RATED (YES/NO): NO	MAX SECTIO	N HEIGHT: 24"	CHECK	(ED	
	MODELS 5740/5760/190/490/7560/591-596/599						
DIVISION OF OVERHEAD DOOR CORP							
3395 ADDISON DRIVE PENSACOLA, FLORIDA 32514 (850) 474—9890		SPECIFICATION	OPTION	CODE 26	1	DNA	

STATIC PRESSURE RATINGS

REVISIONS

SCALE: N.T.S.

DATE

03/23/21

SHEET 3 OF 3
DRAWING PART NO.

411828

APPROVED SIZES

SIZE: A

NAME

SW

REV.