


3. VINYL OR WOOD DOOR STOP NAILED A MAXIMUM OF 6" O.C. MUST OVERLAP TOP AND BOTH ENDS OF PANELS MINIMUM 7/16" TO MEET NEGATIVE PRESSURES.

DIMENSIONS SHALL BE 39" X 5-1/6" CUTOUT. GLASS IS NOT

4. KEY LOCK, SLIDE LOCK, OR OPERATOR REQUIRED.

WIND-BORNE DEBRIS REGIONS. DLO = 4"X37.8".

- 5. FACER STEEL TO HAVE A MINIMUM 29 GA THICKNESS AND BACKER STEEL TO HAVE A MINIMUM 29 GA THICKNESS.
- 6. EACH SECTION HAS AN INTERNAL 1" WIDE X 20 GA CONTINUOUS STEEL STRIP AT THE TOP AND BOTTOM OF THE
- 7. DOOR JAMB TO BE MINIMUM 2x6 SOUTHERN PINE LUMBER. REFER TO JAMB CONNECTION SUPPLEMENT FOR ATTACHMENT TO SUPPORTING STRUCTURE.
- 8. FOR LOW HEAD ROOM LIFT CONDITIONS, TOP BRACKET SHALL BE A 13 GA LHR 7/4 TOP BRACKET WITHOUT PUSHNUTS AND WITH A MINIMUM OF (3) 1/4-14x7/8" SELF DRILLING CRIMPTITE SCREWS IN LIEU OF THE BRACKET SHOWN ON THIS DRAWING. U-BAR ON TOP SECTION SHALL BE INSTALLED ON TOP OF LHR TOP BRACKETS.
- 9. MINIMUM 1" OVERLAP ON BOTH JAMBS REQUIRED TO MEET NEGATIVE DESIGN PRESSURES.
- 10. COMPLIES WITH THE REQUIREMENTS OF IBC/IRC 2018.



		PRESSURE STRUCTURE
DOOR		

DOOR WIDTH	DOOR HEIGHT	UNIFORM LOAD EACH JAMB (PLF)
17'-2"	ALL	+214.6/-242.1
18'-2"	ALL	+227.1/-256.2

	LJAMB BRACKET SCHEDULE								
DOOR HEIGHT	NO. OF SECTIONS	NO. OF JAMB BRACKETS (EACH JAMB)	LOCATION OF CENTERLINE OF JAMB BRACKETS MEASURED FROM BOTTOM OF TRACK (ALL DIMENSIONS ± 2")						
6'-6"	4	7	2" (JB-US), 10" (JB-US), 21-3/4" (JB-US), 29-3/4" (JB-US), 39" (JB-US), 48" (JB-US), 57-1/4" (JB-US)						
7'-0"	4	7	2" (JB-US), 10" (JB-US), 21-3/4" (JB-US), 29-3/4" (JB-US), 42" (JB-US), 52-1/2" (JB-US), 63-1/4" (JB-US)						
7'-6"	4 OR 5	8	2" (JB-US), 10" (JB-US), 18-3/4" (JB-US), 26-3/4" (JB-US), 36" (JB-US), 45" (JB-US), 54-1/4" (JB-US), 74-1/2" (JB-US						
8'-0"	4 OR 5	8	2" (JB-US), 10" (JB-US), 21-3/4" (JB-US), 29-3/4" (JB-US), 39" (JB-US), 48" (JB-US), 57-1/2" (JB-US), 75-1/2" (JB-US)						
> 8'-0"			SEE NOTE BELOW						

(JB-US) FOLLOWING DIMENSION DENOTES SLOTTED JAMB BRACKET ATTACHED TO TRACK WITH 1/4-20x9/16" TRACK BOLT AND NUT AS SHOWN ABOVE.

ALL DOORS GREATER THAN 8' IN HEIGHT REQUIRE USE OF CONTINUOUS WALL ANGLE, SEE SUPPLEMENT TRACK CHART FOR DETAILS,

ATE OF DWAYNE J KORNISH 117868 .... CENSED. ONAL ENG DWAYNE J. KORNISH, PE 4578 COUNTY ROAD 160 MOUNT HOPE, OHIO FL PE 77845 TX PE 117868 PROFESSIONAL ENGINEER'S SEAL PROVIDED ONLY FOR VERIFICATION OF WINDLOAD CONSTRUCTION DETAILS.

The Genuine. The Original.

•	STATIC PRESSURE RATINGS			APPROVED SIZES SCA			.T.S.	SIZE:	Α
	DESIGN (PSF):	+25.00/-28.20	MAX	MDTH:	18'-2"		DATE	NAM	ΙE
7	TEST (PSF):	+37.50/-42.30	MAX	HEIGHT:	24'-0"	DRAWN	03/23/21	SW	ı
	IMPACT/CYCLIC	RATED (YES/NO): YES	MAX	SECTION	HEIGHT: 24"	CHECKED			
	MODEL		SHEET 1 C	F 3					


DIVISION OF OVERHEAD DOOR CORF 3395 ADDISON DRIVE PENSACOLA, FLORIDA 32514 (850) 474-9890


MODELS 5/40/5/60/190/490//560/591-596/59 DRAWING PART NO. REV. WINDLOAD SPECIFICATION OPTION CODE 2616 411836

**REVISIONS** 


- RELEASE DRAWING

SW 3/23/2021






	OUTSIDE FRAME SIZE	DAYLIGHT OPENING (DLO)	SCREW QTY EA HORIZ LEG	SCREW QTY EA VERT LEGS	SCREW QTY TOTAL	DETAIL
	17"X51"	14X48	5	3	16	G
	15.1X44"	11.5"X40.5"	8	3	22	Н
L	14.9X20.8"	11"X17"	3	3	12	Н
	7"X40.8	4"X37.8"	5	2	14	Н
	15.3"X44.1"	11.3"X40.1"	6	3	18	-
Г	14.6"X20.8"	10.6"X16.8"	3	2	10	1
Г	13"X38"	9"X34"	5	2	14	1



STATIC PRESSURE RATINGS



The Genuine. The Original.

DES

TES

IMP/

A DIVISION OF OVERHEAD DOOR CORP
3395 ADDISON DRIVE
PENSACOLA, FLORIDA 32514
(850) 474—9890

	DESIGN (PSF): +25.00/-28.20 MAX WIDTH: 18'-2"		2"		DATE	NAME			
Ţ	TEST (PSF):	+37.50/-42.30	MAX HEIGH	IT: 24'-	0" DRA	WN	03/23/21	:	SW
<u> </u>	IMPACT/CYCLIC	RATED (YES/NO): YES	MAX SECT	ON HEIGHT	T: 24" CHE	CKED			
	MODELS 5740/5760/190/490/7560/591-596/599						SHEET 3 0	F 3	
ORP			•	·		DR	AWING PART	NO.	REV.
	WINDLOAD	SPECIFICATION	OPTION	CODE	2616		411836		_

APPROVED SIZES | SCALE: N.T.S.

SIZE: A

REVISIONS