1. VINYL OR WOOD DOOR STOP NAILED A MAXIMUM OF 6" O.C. MUST OVERLAP TOP AND BOTH ENDS OF PANELS MINIMUM 7/16" TO MEET NEGATIVE PRESSURÉS. 2. SLIDE LOCK OR OPERATOR REQUIRED. LOW HEADROOM REQUIRES A LOCK ON THE LEFT AND RIGHT SIDE OF THE DOOR. 3. THE DESIGN OF THE SUPPORTING STRUCTURAL ELEMENTS SHALL BE THE RESPONSIBILITY OF THE BUILDING OR STRUCTURE AND IN ACCORDANCE WITH CURRENT


PROFESSIONAL OF RECORD FOR THE BUILDING CODES FOR THE LOADS LISTED ON THIS DRAWING.

4. SECTION STEEL TO HAVE THE FOLLOWING MINIMUM THICKNESS: EXTERIOR - 27 GA INTERIOR - 30 GA

5. DOOR JAMB TO BE MINIMUM 2x6 STRUCTURAL GRADE LUMBER AND BE SPRUCE, PINE, OR FIR. REFER TO JAMB CONNECTION SUPPLEMENT FOR ATTACHMENT TO SUPPORTING STRUCTURE.

6. FOR LOW HEAD ROOM LIFT CONDITIONS, TOP BRACKET SHALL BE A LHR TOP BRACKET IN LIEU OF THE BRACKET SHOWN ON THIS DRAWING, SEE LHR, DETAIL A, SHEET

7. 11 GA ROLLER SLIDES WITH WELDED ENDS AND 11 GA REINFORCING BRACKETS REQUIRED FOR DOORS > 8' TALL.



JOHN E. SCATES, PE 2560 KING ARTHUR #124-54 LEWISVILLE, TX 75056 FL PE 51737 TX PE 56308/F-2203

LOADS ON SUPPORTING STRUCTURE DOOR DOOR UNIFORM LOAD EACH JAMB (PLF) HEIGHT WIDTH 9'-0" ALL +103.1/-118.4 8'-0" ALL +91.6/-105.2

PROFESSIONAL ENGINEER'S SEAL PROVIDED ONLY FOR VERIFICATION OF WINDLOAD CONSTRUCTION DETAILS.



DIVISION OF OVERHEAD DOOR COR 3395 ADDISON DRIVE PENSACOLA, FLORIDA 32514 (850) 474-9890

| STATIC PRESSURE RATINGS | | APPROVED SIZES | | | SCALE: N.T.S. | | SIZE: A |
|-------------------------------|--------------------|----------------|---------|-------------|---------------|---------|---------|
| DESIGN (PSF): | +22.90/-26.30 | MAX | WIDTH: | 9'-0" | | DATE | NAME |
| | | MAX | HEIGHT: | 14'-0" | DRAWN | 1/11/06 | GRT |
| IMPACT/CYCLIC | RATED (YES/NO): NO | MAX | SECTION | HEIGHT: 28" | CHECKED | 2/10/06 | MRB |
| MODELS 9700/9510 SHEET 1 OF 2 | | | | | | | |

MODELS 9/00/9510 WINDLOAD SPECIFICATION OPTION CODE 0502

DRAWING PART NO. REV. 313585 Н

REVISIONS

P5 CHANGES MADE

PER ETC

BLOCK 4/15/13 GRT

LABORATORIES

GENERAL FORMAT

P6 UPDATED TITLE

P7 UPDATED AS PER

UPDATED PER

GENERAL FORMAT

TESTING AND

CHANGES TO

1/11/06 GRT

TESTING AND

CHANGES TO

8-19-16 GAC

PCR32744.

LEVELS TO ALPHABETICAL

UPDATED REV

12/8/21 SW

