REVISIONS				
REV	DESCRIPTION	DATE	APPROVED	
С	REVISED PER NEW REQUIREMENTS	07/21/2022	R.L.	

NOTES:

- 1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH REQUIREMENTS OF THE 2018 IBC AND 2018 IRC.
- 2. WOOD FRAMING AND MASONRY OPENING TO BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO STRUCTURE. FRAMING AND MASONRY OPENING IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
- 3. ALLOWABLE STRESS INCREASE OF 1/3 WAS NOT USED IN THE DESIGN OF THE PRODUCT SHOWN HEREIN. WIND LOAD DURATION FACTOR Cd=1.6 WAS USED FOR WOOD ANCHOR CALCULATIONS.
- 4. BUCKS SHALL EXTEND BEYOND UNIT FRAME INTERIOR FACE SO THAT FULL FRAME SUPPORT IS PROVIDED.
- 5. FRAME MATERIAL: EXTRUDED RIGID PVC.
- 6. UNITS MUST BE GLAZED PER ASTM E1300, SEE SHEET 2 FOR GLASS DETAILS.
- 7. APPROVED IMPACT PROTECTIVE SYSTEM <u>IS NOT REQUIRED</u> FOR THIS PRODUCT IN WIND BORNE DEBRIS REGIONS.
- 8. SHIM AS REQUIRED AT EACH INSTALLATION ANCHOR WITH LOAD BEARING SHIM. SHIM WHERE SPACE OF 1/16" OR GREATER OCCURS. MAXIMUM ALLOWABLE SHIM STACK TO BE 1/4".
- 9. FOR ANCHORING INTO WOOD FRAMING OR 2X BUCK USE #10 WOOD SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/4" MINIMUM EMBEDMENT INTO SUBSTRATE. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
- 10. FOR ANCHORING INTO MASONRY/CONCRETE USE 3/16" TAPCONS WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/4" MINIMUM EMBEDMENT INTO SUBSTRATE WITH 2" MINIMUM EDGE DISTANCE. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
- 11. FOR ANCHORING INTO METAL STRUCTURE USE #10 SMS OR SELF DRILLING SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE 3 THREADS MINIMUM BEYOND STRUCTURE INTERIOR WALL. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
- 12. ALL FASTENERS TO BE CORROSION RESISTANT.
- 13. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BELOW:

 A. WOOD MINIMUM SPECIFIC GRAVITY OF G=0.42
 - B. CONCRETE MINIMUM COMPRESSIVE STRENGTH OF 3,192 PSI.
 - C. MASONRY STRENGTH CONFORMANCE TO ASTM C-90, GRADE N, TYPE 1 (OR GREATER).

SHEET NO.

2

3 - 5

6

NOTES

- D. METAL STRUCTURE: STEEL 18GA, 33KSI OR ALUMINUM 6063-T5 1/8" THICK MINIMUM
- 14. APPROVED CONFIGURATIONS: OX AND XO

SIGNED: 07/21/2022

REGENCY PLUS, INC.

2000 LOCUST GAP HIGHWAY

MT. CARMEL, PA 17851

SERIES 6412 VINYL HORIZONTAL SLIDING WINDOW 74" X 63" — IMPACT NOTES

DRAWN: DWG NO. REV
V.L. 08-01715 C

SCALE NTS DATE 09/17/12 SHEET 1 OF 6

L. ROBERTO LOMAS P.E. 400 S. PALM AVE, INDIALANTIC, FL 32903 434-688-0609 rllomas@lrlomaspe.com



Luis R. Lomas P.E. TX No.: 101889 Firm No: F-23130



TABLE OF CONTENTS


ELEVATION AND GLAZING DETAIL

INSTALLATION DETAILS

COMPONENTS

DESCRIPTION

REVISIONS				
REV	DESCRIPTION	DATE	APPROVED	
С	REVISED PER NEW REQUIREMENTS	07/21/2022	R.L.	




SERIES 6412 VINYL HORIZONTAL SLIDING WINDOW EXTERIOR VIEW

DESIGN PRESSURE RATING	IMPACT RATING
+45.0/-50.0PSF	LARGE AND SMALL MISSILE IMPACT


MISSILE LEVEL D, WIND ZONE 4

NOTES:

- 1. MAXIMUM PANEL SIZE: 36 1/4" X 60"
- 2. MAXIMUM PANEL D.L.O.: 32 1/4" X 56 1/2"
- 3. MAXIMUM FIXED LITE D.L.O.: 33" X 57 1/2"





SIGNED: 07/21/2022







Luis R. Lomas P.E. TX No.: 101889 Firm No: F-23130










REVISIONS				
REV	DESCRIPTION	DATE	APPROVED	
С	REVISED PER NEW REQUIREMENTS	07/21/2022	R.L.	










PROFILE SASH (1282)
RIGID PVC










INTERLOCK COVER (1180)
RIGID PVC














SIGNED: 07/21/2022





Luis R. Lomas P.E. TX No.: 101889 Firm No: F-23130