

WINCORE™

WINDOWS & DOORS

250 Staunton Turnpike, Parkersburg, WV 26104

500 Series Vinyl Double Hung Window w/ Nailing Fin "NON-IMPACT"

EVALUATED FOR USE IN THE STATE OF TEXAS


TDI WIN-1898

The Wincore Double Hung Window described herein complies with the 2018 International Residential Code (IRC), Sections R301 & R609 and the 2018 International Building Code (IBC), Sections 1404.13, 1609, 1709.5, 2403 and 2404 subject to the following conditions:


1. Anchors shall be as listed and spaced as shown in the details. Anchor embedment to base material shall be beyond wall dressing or stucco.
2. When used in areas requiring wind-borne debris protection this product is required to be protected with an impact resistant covering that complies with Section R301.2.1.2 of the IRC and Section 1609.1.2 of the IBC.
3. Allowable design pressure requirements must be equal to or less than the design pressure rating shown in the design pressure chart, sheet 1 of this drawing.
4. Conditions not covered by this drawing are subject to further engineering analysis.

TABLE OF CONTENTS

SHEET#	DESCRIPTION
1	Typical elevations, design pressures & general notes
2	Vertical & horizontal cross sections & frame anchoring
3	Bill of materials & components



MAX. FRAME DIMENSION	MAX. D.L.O. DIMENSION	GLASS TYPE	REINFORCEMENT LOCATIONS	DESIGN PRESSURE (PSF)	
				POSITIVE	NEGATIVE
44.0" X 60.0"	38.25" X 26.38"	G1	None	+35.0	-35.0
32.0" X 78.0"	26.25" X 35.38"	G1	None	+45.0	-45.0
40.0" X 68.0"	34.25" X 30.38"	G2	None	+30.0	-30.0
52.0" X 63.0"	46.25" X 27.88"	G1	Mtg. Rail / Lock Rail	+30.0	-30.0
36.0" X 68.0"	30.25" X 30.38"	G1	All Rails & Stiles	+50.0	-50.0
38.0" X 59.0"	32.25" X 25.88"	G1	Mtg. Rail / Lock Rail	+50.0	-50.0
46.0" X 77.0"	40.25" X 34.88"	G1	All Rails & Stiles	+35.0	-35.0



Documents Prepared By: Lyndon F. Schmidt, P.E.
TEXAS P.E. #104123

RW BUILDING CONSULTANTS, INC.
P.O. Box 230 Valrico FL 33595
Phone No.: 813.659.9197

TEXAS BOARD OF PROFESSIONAL ENGINEERS
CERTIFICATE OF REGISTRATION # F-11852

PRODUCT: 500 SERIES Vinyl Double Hung Window

PART OR ASSEMBLY: TYPICAL ELEVATION, DESIGN PRESSURES & GENERAL NOTES

NO.	DATE	REVISIONS
2	1/20/20	UPDATE TO 2018 IBC/IRC
1	2/09/16	ADD NEW FRAME SIZES

DATE: 8/14/13

SCALE: N.T.S.



DWG. BY: JK

CHK. BY: LFS


DRAWING NO.: TX-4345

SHEET 1 OF 3


2x framing to be designed by the engineer or architect of record based on wind loads and the cladding being used.



1 HORIZONTAL CROSS SECTION
3 Stud Construction



2 VERTICAL CROSS SECTION
3 Stud Construction



Documents Prepared By: Lyndon F. Schmidt, P.E.
TEXAS P.E. #104123

RW BUILDING CONSULTANTS, INC.
P.O. Box 230 Valrico FL 33595
Phone No.: 813.659.9197


















TEXAS BOARD OF PROFESSIONAL ENGINEERS
CERTIFICATE OF REGISTRATION # F-11852

PRODUCT:	500 SERIES Vinyl Double Hung Window
PART OR ASSEMBLY:	VERTICAL & HORIZONTAL CROSS SECTIONS & FRAME ANCHORING
DATE:	8/14/13
SCALE:	N.T.S.
DWG. BY:	JK
CHK. BY:	LFS
DRAWING NO.:	TX-4345
SHEET	2 OF 3

NO.	DATE	REVISIONS
2	1/20/20	UPDATE TO 2018 IBC/IRC
1	2/09/16	ADD NEW FRAME SIZES

BILL OF MATERIALS		
ITEM #	DESCRIPTION	MATERIAL
B	2X BUCK SG >= 0.42	WOOD
C	1/4" MAX. SHIM SPACE	-
G	#8 X 2-1/2" PPH WOOD SCREW	STEEL
1	FRAME JAMB*	PVC
2	SILL*	PVC
3	FRAME HEAD*	PVC
4	TOP RAIL UPPER SASH*	PVC
5	KEEPER RAIL UPPER SASH*	PVC
6	GLAZING BEAD*	PVC
7	LOCK RAIL LOWER SASH*	PVC
8	LOWER SASH STILE*	PVC
10	REINFORCEMENT (6005-T5) ALUM	ALUM
11	REINFORCEMENT (6005-T5) ALUM	ALUM
12	BOTTOM RAIL LOWER SASH*	PVC
14	REINFORCEMENT (6005-T5) ALUM	ALUM
15	REINFORCEMENT (6005-T5) ALUM	ALUM
16	WEATHERSTRIP ULTRA FAB .270 PILE - 270 -1875B	-
17	WEATHERSTRIP SILLBULB (AMESBURY 32690)	-
20	LOCK	-
21	KEEPER	-
26	#8 X 1" TEK SCREW	STEEL

* THE APPROVED WHITE RIGID PVC EXTERIOR EXTRUSIONS FOR WINDOWS ARE TO BE PRODUCED BY EXTRUDERS LICENSEES IN "AAMA CERTIFICATION PROGRAMS FOR RIGID PVC EXTRUSIONS".



Documents Prepared By: Lyndon F. Schmidt, P.E.
TEXAS P.E. #104123

RW BUILDING CONSULTANTS, INC.
P.O. Box 230 Valrico FL, 33595
Phone No.: 813.659.9197

TEXAS BOARD OF PROFESSIONAL ENGINEERS
CERTIFICATE OF REGISTRATION # F-11852

PRODUCT:	500 SERIES Hung Window
PART OR ASSEMBLY:	Vinyl Double Hung Window
COMPONENTS:	
DATE:	8/14/13
SCALE:	N.T.S.
DWG. BY:	JK
CHK. BY:	LFS
DRAWING NO.:	TX-4345
SHEET	3 OF 3