	REVISIONS				
REV	DESCRIPTION	DATE	APPROVED		
А	REVISED PER NEW REQUIREMENTS	07/31/19	R.L.		
В	REVISED PER NEW CODE	10/25/2021	R.L.		

## NOTES:

- 1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH REQUIREMENTS OF THE 2018 IBC AND 2018 IRC.
- 2. WOOD FRAMING AND MASONRY OPENING TO BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO STRUCTURE. FRAMING AND MASONRY OPENING IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
- 3. 1X BUCK OVER MASONRY/CONCRETE IS OPTIONAL.
- 4. WHERE SHIM OR BUCK THICKNESS IS LESS THAN 1-1/2" WINDOW UNITS MUST BE ANCHORED THROUGH THE FRAME IN ACCORDANCE WITH MANUFACTURER'S PUBLISHED INSTALLATION INSTRUCTIONS. ANCHORS SHALL BE SECURELY FASTENED DIRECTLY INTO MASONRY, CONCRETE OR OTHER STRUCTURAL SUBSTRATE MATERIAL.
- 5. WHERE WOOD BUCK THICKNESS IS 1-1/2" OR GREATER, BUCK SHALL BE SECURELY FASTENED TO MASONRY, CONCRETE OR OTHER STRUCTURAL SUBSTRATE. WINDOW UNITS MAY BE ANCHORED THROUGH FRAME TO SECURED WOOD BUCK IN ACCORDANCE WITH MANUFACTURER'S PUBLISHED INSTALLATION INSTRUCTIONS.
- 6. WHERE 1X BUCK IS NOT USED DISSIMILAR MATERIALS MUST BE SEPARATED WITH APPROVED COATING OR MEMBRANE. SELECTION OF COATING OR MEMBRANE IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
- 7. BUCKS SHALL EXTEND BEYOND WINDOW INTERIOR FACE SO THAT FULL FRAME SUPPORT IS PROVIDED.
- 8. FOR FIN INSTALLATION SHIM AS NEEDED. FOR FRAME INSTALLATION SHIM AS REQUIRED AT EACH ANCHOR LOCATION WITH LOAD BEARING SHIM. SHIM WHERE SPACE OF 1/16" OR GREATER OCCURS. MAXIMUM ALLOWABLE SHIM STACK TO BE 1/4".
- 9. SHIMS SHALL BE LOCATED, APPLIED AND MADE FROM MATERIALS AND THICKNESS CAPABLE OF SUSTAINING APPLICABLE LOADS.
- 10. WIND LOAD DURATION FACTOR Cd=1.6 WAS USED FOR WOOD ANCHOR CALCULATIONS.
- 11. FRAME MATERIAL: EXTRUDED RIGID PVC.
- 12. UNITS MUST BE GLAZED PER ASTM E1300.
- 13. APPROVED IMPACT PROTECTIVE SYSTEM <u>IS REQUIRED</u> FOR THIS PRODUCT IN WIND BORNE DEBRIS REGIONS.
- 14. FOR FIN ANCHORING INTO WOOD FRAMING OR 2X BUCK USE #8 WOOD SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/4" MINIMUM EMBEDMENT INTO SUBSTRATE. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.

- 15. FOR FRAME ANCHORING INTO WOOD FRAMING OR 2X BUCK USE #10 WOOD SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/4" MINIMUM EMBEDMENT INTO SUBSTRATE. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
- 16. FOR FRAME ANCHORING INTO MASONRY/CONCRETE USE 3/16" TAPCONS WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/4" MINIMUM EMBEDMENT INTO SUBSTRATE WITH 2" MINIMUM EDGE DISTANCE. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
- 17. FOR FRAME ANCHORING INTO METAL STRUCTURE USE #10 SMS OR SELF DRILLING SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE 3 THREADS MINIMUM BEYOND STRUCTURE INTERIOR WALL. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
- 18. ALL FASTENERS TO BE CORROSION RESISTANT.
- 19. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BELOW:
  - A. WOOD MINIMUM SPECIFIC GRAVITY OF G=0.42
  - B. CONCRETE MINIMUM COMPRESSIVE STRENGTH OF 3,192 PSI.
  - C. MASONRY STRENGTH CONFORMANCE TO ASTM C-90, GRADE N, TYPE 1 (OR GREATER).
  - D. METAL STRUCTURE: STEEL 18GA, 33KSI OR ALUMINUM 6063-T5 1/8" THICK MINIMUM


SIGNED: 11/16/2021

			WINDOW MART 5760 ALBERT PIKE ROYAL, AR 71968 7500 PICTURE WINDOW NON-IMPACT NOTES			
	TADLE OF CONTENTS					
	TABLE OF CONTENTS					
SHEET NO.	DESCRIPTION	DRAWN:		DWG NO.		REV
1	NOTES	J.L.	J.L. 08-02325		В	
2	ELEVATIONS	SCALE NTS	DATE 05	5/15/14	SHEET 1 OF 6	
3 - 5	INSTALLATION DETAILS		L. ROBERTO LOMAS P.E. 1432 WOODFORD RD LEWISVILLE, NC 27023 434-688-0609 rllomas@lrlomaspe.com			
6	COMPONENTS					


LUIS LOWNS


Luis R. Lomas P.E. TX No.: 101889


REVISIONS				
REV	DESCRIPTION	DATE	APPROVED	
А	REVISED PER NEW REQUIREMENTS	07/31/19	R.L.	
В	REVISED PER NEW CODE	10/25/2021	R.L.	





SIGNED: 11/16/2021












## NOTES:

1. INTERIOR AND EXTERIOR FINISHES, BY OTHERS, NOT SHOWN FOR CLARITY.

2. PERIMETER AND JOINT SEALANT BY OTHERS TO BE DESIGNED IN ACCORDANCE WITH ASTM E2112

D IN ACCORDANCE WITH ASTM E2112	SIGNED: 11/16/2021
WINDOW MART 5760 ALBERT PIKE ROYAL, AR 71968	TO THE OF THE PARTY OF THE PART
7500 PICTURE WINDOW NON-IMPACT INSTALLATION DETAILS	101889
DRAWN: DWG NO. REV  J.L. 08-02325 B	A POLONY ENGINEER
CALE NTS DATE 05/15/14 SHEET 5 OF 6	
L. ROBERTO LOMAS P.E. 1432 WOODFORD RD LEWISVILLE, NC 27023 434-688-0609 rllomas@lrlomaspe.com	Luis R. Lomas P.E. TX No.: 101889



1 1/4" MIN.

EMBEDMENT

WOOD FRAMING

BY OTHERS

1/4" MAX. SHIM SPACE

APPROVED -SEALANT


BEHIND FIN


7/16" MIN

EDGE DISTANCE

#8 WOOD

SCREW









SIGNED: 11/16/2021

APPROVED

R.L.

DATE

07/31/19

10/25/2021 R.L.

REVISIONS

DESCRIPTION

REVISED PER NEW REQUIREMENTS

REVISED PER NEW CODE

WINDOW MART 5760 ALBERT PIKE ROYAL, AR 71968					
7500 PICTURE WINDOW NON-IMPACT COMPONENTS					
DRAWN:		DWG NO.			REV
J.L.		08-02325		В	
SCALE NTS	DATE O	5/15/14	SHEET 6	OF 6	
L. ROBERTO LOMAS P.E. 1432 WOODFORD RD LEWISVILLE, NC 27023 434-688-0609 rllomas@Irlomaspe.com					



Luis R. Lomas P.E. TX No.: 101889