

PO Box 12030 | Austin, TX 78711 | 800-578-4677 | tdi.texas.gov

# **Product Evaluation**

### WIN1229 | 0424

**Engineering Services Program** 

The following product has been evaluated for compliance with the wind loads specified in the International Residential Code (IRC) and the International Building Code (IBC).

This product evaluation is not an endorsement of this product or a recommendation that this product be used. The Texas Department of Insurance has not authorized the use of any information contained in the product evaluation for advertising, or other commercial or promotional purpose.

This product evaluation is intended for use by those individuals who are following the design wind load criteria in Chapter 3 of the IRC and Section 1609 of the IBC. The design loads determined for the building or structure shall not exceed the design load rating specified for the products shown in the limitations section of this product evaluation. This product evaluation does not relieve a Texas licensed engineer of his responsibilities as outlined in the Texas Insurance Code, the Texas Administrative Code, and the Texas Engineering Practice Act.

For more information, contact TDI Engineering Services Program at (800) 248-6032.

**Evaluation ID:** WIN-1229 **Effective Date:** April 1, 2024

**Re-evaluation Date:** April 2028

Product Name: C100 Vinyl Operating Casement Windows, Fin and Frame Installation, Non-

**Impact Resistant** 

Manufacturer: NT Windows, Inc.

2900 Seminary Drive Fort Worth, TX 76133 (800) 969-8830

### **General Description:**

2000.000				
System	Description	Label Rating	<b>Design Pressure Rating</b>	
1	C100 Vinyl Operating Casement Windows; Fin Installation	LC-PG60 (36 x 72)-C	+60 / -60 psf	
2	C100 Vinyl Operating Casement Windows; Frame Installation	LC-PG50 (36 x 72)-C	+50 / -50 psf	

### **Product Dimensions:**

System	Overall Size	Operating Sash Size
1	36" x 72"	34-1/8" x 70-1/8"
2	36" x 72"	34-1/8" x 70-1/8"

# **Product Identification (Certification Agency Label on Window):**

System		
1, 2	Certification Agency	AAMA
	Manufacturer's Name or Code Name	NT-1
	Product Name	C100 Casement
	Test Standards	AAMA/WDMA/CSA 101/I.S.2/A440-08

**Compliance:** The products comply with AAMA/WDMA/CSA 101/I.S.2/A440-17 as referenced in the 2018 IRC and 2018 IBC.

## **Impact Resistance:**

System	Impact Resistant	Requirement	
1, 2	No	These products have not been tested for windborne debris resistance. An impact protection system is required when installing this product in areas where windborne debris protection is required.	

## **Installation:**

System			
1	Type of Installation	Frame Installation	
	Wall Framing	Spruce-Pine-Fir dimension lumber	
	Fasteners	Minimum No. 8 x 2-1/2" screws	
	Fastener Location/Spacing	Along each side jamb, located approximately	
		5" from each corner and one at the midspan	
	Fastener Penetration	Minimum of 1-1/2" into the wall framing	
2	Type of Installation	Nail Fin Installation	
	Wall Framing	Spruce-Pine-Fir dimension lumber	
	Fasteners	No. 6 x 1-1/4" drywall screws	
	Fastener Location/Spacing	Approximately 2" from each corner and 10" on	
		center along the perimeter	
	Fastener Penetration	Minimum of 1-1/2" into the wall framing	

**Note:** Keep the manufacturer's installation instructions available on the job site during installation. Use corrosion resistant fasteners as specified in the IRC and the IBC.